

AD-A093 929

ARNOLD ENGINEERING DEVELOPMENT CENTER ARNOLD AFS TN  
LASER SCATTERING APPLICATIONS DEVELOPMENT TEST IN AEDC TUNNEL B--ETC(U)  
MAR 80 W T STRIKE, L L PRICE

F/G 14/2

UNCLASSIFIED

AEDC-TSR-80-V16

NL

1 OF 1  
2013-09-09

SEARCHED




END  
DATE FILMED  
2-84  
DTIC

AEDC-TSR-80-V16

LEVEL 2

LASER SCATTERING APPLICATIONS DEVELOPMENT TEST IN  
AEDC TUNNEL B AT MACH NUMBER 8

AD A093929



W. T. Strike and L. L. Price  
ARO, Inc.

March 1980

Final Report for Period January 16, 1980 to February 12, 1980

Approved for public release; distribution unlimited.



FILE COPY  
DDC

ARNOLD ENGINEERING DEVELOPMENT CENTER  
ARNOLD AIR FORCE STATION, TENNESSEE  
AIR FORCE SYSTEMS COMMAND  
UNITED STATES AIR FORCE

81 1 19 079

#### NOTICES

When U. S. Government drawings, specifications, or other data are used for any purpose other than a definitely related Government procurement operation, the Government thereby incurs no responsibility nor any obligation whatsoever, and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise, or in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

References to named commercial products in this report are not to be considered in any sense as an endorsement of the product by the United States Air Force or the Government.

#### APPROVAL STATEMENT


This report has been reviewed and approved.



LARRY M. DAVIS, 2d Lt, USAF  
Test Director, VKF Division  
Directorate of Test Operations

Approved for publication:

FOR THE COMMANDER



JOHN C. HARTNEY, Colonel USAF  
Director of Test Operations  
Deputy for Operations

## UNCLASSIFIED

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER AEDC-TSR-80-V16	2. GOVT ACCESSION NO. AD-A093929	3. RECIPIENT'S CATALOG NUMBER 9	
4. TITLE (and Subtitle) LASER SCATTERING APPLICATIONS DEVELOPMENT TEST IN AEDC TUNNEL B AT MACH NUMBER 8		5. TYPE OF REPORT PERIOD COVERED Final Report Jan. 16-Feb. 12, 1980	
6. PERFORMING ORG. REPORT NUMBER			
7. AUTHOR(s) W. T. Strike and L. L. Price ARO, Inc., a Sverdrup Corporation Company		8. CONTRACT OR GRANT NUMBER(s)	
9. PERFORMING ORGANIZATION NAME AND ADDRESS Arnold Engineering Development Center/D0 Air Force Systems Command Arnold Air Force Station, TN 37389		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Program Element 65807F	
11. CONTROLLING OFFICE NAME AND ADDRESS Arnold Engineering Development Center/DOT Air Force Systems Command Arnold Air Force Station, TN 37389		12. REPORT DATE March 1980	
13. NUMBER OF PAGES 47		14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)	
15. SECURITY CLASS. (of this report) UNCLASSIFIED		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE N/A	
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.			
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
18. SUPPLEMENTARY NOTES  Available in Defense Technical Information Center (DTIC).			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) laser scattering measure surface press data Fabry-Perot interferometer wind tunnel test			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Free stream and local flow field measurements on a blunt (0.375-in. radius) nose 5-deg cone were made in Tunnel B at Mach number 8. The nonintrusive flow field measurements were made using various laser scattering optical systems to determine the free stream and local flow field particulate concentration and size distribution, the nitrogen molecule number density, and the local stream velocity using a Fabry-Perot interferometer system. The 5-deg cone pressure distributions were used to confirm the test section Mach number and to produce a known local flow field which could be used to demonstrate potentially con.			

UNCLASSIFIED

042550 *AM*

**UNCLASSIFIED**

20. ABSTRACT

cont. useful laser scattering measuring techniques.

Accession for  
MIG 6748  
MIG 6749  
Uncontrolled  
Classification

Approved by \_\_\_\_\_  
Date \_\_\_\_\_  
Approved by \_\_\_\_\_  
Date \_\_\_\_\_  
Approved by \_\_\_\_\_  
Date \_\_\_\_\_

*[Handwritten signature]*

**UNCLASSIFIED**

## CONTENTS

	<u>Page</u>
NOMENCLATURE . . . . .	2
1.0 INTRODUCTION . . . . .	4
2.0 APPARATUS	
2.1 Test Facility . . . . .	5
2.2 Test Article . . . . .	5
2.3 Laser-Scattering System . . . . .	6
2.4 Standard Test Instrumentation . . . . .	7
3.0 TEST DESCRIPTION	
3.1 Test Conditions and Procedures	
3.1.1 General . . . . .	7
3.1.2 Test Procedure . . . . .	8
3.1.3 Data Acquisition . . . . .	8
3.2 Data Reduction . . . . .	8
3.3 Measurement Uncertainty . . . . .	9
4.0 DATA PACKAGE PRESENTATION . . . . .	9
REFERENCES . . . . .	10

## APPENDIXES

### I. ILLUSTRATIONS

#### Figure

1. Tunnel B . . . . .	12
2. VKF Standard Cone-Pressure Model . . . . .	13
3. Tunnel B Installation for Laser Scattering Test . . . . .	14
4. Laser-Photomultiplier Detector Installation with Model Injected . . . . .	15
5. Dual Laser Installation, Nonoperating Side of Tunnel B . .	16
6. Laser-Optics Installation on the Operating Side of Tunnel B	19
7. Laser-Optics System as Viewed from within the Tunnel, Operating Side . . . . .	23
8. Laser-Optics System as Viewed from within the Tunnel, Nonoperating Side . . . . .	24
9. Optical Recording System on Top of Tunnel B . . . . .	25
10. 5-Deg Blunt Cone (Calibration Body) Pressure Distributions	27

### II. TABLES

1. Estimated Uncertainties . . . . .	37
2. VKF Tunnel B Test Log . . . . .	30

### III. DATA PACKAGE FORMATS

1. Typical Pressure Distribution Tabulations . . . . .	44
2. Typical Laser-Optics Tabulations . . . . .	46

## NOMENCLATURE

ALPHA, $\alpha$	Sector Angle (prebend angle was 12.0 deg), deg
C.R.	Center of Rotation, in.
DATA TYPE	Defines the type of measurement and the sampling procedure <ol style="list-style-type: none"> <li>1. Laser data consisting of 300 samples at 0.03 sec between points</li> <li>2. Pressure data consisting of 40 samples at usually 1.0 sec between points</li> </ol>
K	Weighting factor for the time constant in the pressure prediction routine, in. <sup>2</sup> /(lbf-sec)
LILM	Laser internal light meter output, mv
LRPM	Laser receiver power meter output, mv
M	Free stream Mach number
OMEGA, PHI	Angular circumferential station, deg
P	Free stream static pressure, psia
PDn	Output of photomultiplier detector number "n", mv
PNN, PPN	Measured model nose local stagnation surface pressure, psia
PREF	Reference pressure, uHg
PRMS	Root-mean-square of the curve fitted time history of the pressure with respect to the measured pressure-time history, psi
PT	Stilling chamber pressure, psia
PT2, PTS	Computed stagnation pressure downstream of a normal shock, psia
PW	Model surface pressure, psia
PWI	Initial pressure measured in the time history of the stabilizing model surface pressure, psia
PWF	Final pressure measured in the time history of the stabilizing model surface pressure, psia
RATIO	Ratio of LRPM/LILM in percent
RE	Reynolds number per ft

RHO	Free stream static density, lbm/ft <sup>3</sup>
RN	Blunt nose cone radius (0.375 in.), in.
S	Cone surface length relative to the blunt nose stagnation point, in.
TOUT	Nitrogen concentration output
TT	Stilling chamber total temperature, °R
U	Free stream velocity, ft/sec
X	Model station measured from theoretical apex of the blunt 5 deg cone, in.

## 1.0 INTRODUCTION

The work reported herein was conducted by the Arnold Engineering Development Center (AEDC), Air Force Systems Command (AFSC), under Program Element 65807F, for the Director of Technology (DOT) at AEDC. The DOT project manager was Capt. Ken Leners and the ARO, Inc. project monitor was Mr. L. L. Price. The results were obtained by ARO, Inc., AEDC Group (a Sverdrup Corporation Company), operating contractor for the AEDC, AFSC, Arnold Air Force Station, Tennessee. The test was conducted in the von Karman Gas Dynamics Facility (VGF), Hypersonic Wind Tunnel (B) during the period January 16, 1980 to February 12, 1980 under ARO Project No. V41B-45.

This test program is to support the research effort entitled "Laser Scattering Applications." The research effort is concerned with the development of laser scattering applications to be used in satisfying future AEDC test requirements. One task in this research effort is the development and application of advanced laser scattering optical systems to measure flow field properties in the VGF supersonic/hypersonic wind tunnels. This experimental phase of the program will be used to provide the data needed to identify the particulate concentration and size distribution in the tunnel flow. Subsequently, this information concerning the tunnel flow particulate characteristics will determine the feasibility of making conventional laser velocimeter measurements in the VGF wind tunnels without "seeding" the flow.

Therefore, the primary objective of this test program was to obtain laser-Mie scattering measurements in Tunnel B which will be used to define flow field particulate concentration and size distribution. In an attempt to fully utilize this tunnel entry and the effort expended to install the laser optical systems, the test objectives were expanded to make the following measurements and laser scattering measurement applications. Using the laser Raman scattering system, measurements were obtained for use in defining the local number density (nitrogen molecules per cu. cm.) in the free stream and downstream of the bow wave of a blunt 5-deg cone. Using this same laser scattering system, the effects of tunnel humidity on flow field measurements were examined. And finally, using a Fabry-Perot interferometer system, the feasibility of making velocity measurements based on a direct Doppler shift measurement, in place of the more conventional laser velocimeter technique requiring tunnel flow seeding, was tested. In summary, the test objectives included an evaluation of the test section flow properties and the application of various scattering measurement techniques.

These tests were conducted in Tunnel B at Mach Number 8 over the Reynolds number range of 0.5 to 3.0 million per foot. Measurements were obtained with and without the dryers in the wind tunnel circuit which produced a maximum (humidity) dew point of nominally 30°F and a minimum (humidity) frost point of -60°F. The pressure distribution on a blunt 5-deg cone (the VGF standard calibration body) was used to monitor the tunnel Mach number.

The observation volume of the laser scattering optics was positioned on the tunnel centerline in the center of the test section. With the model injected, this observation volume fell downstream of the blunt 5-deg cone bow wave, but above the model surface. The location of the observation volume relative to the model was varied by changing the vertical position of the model. At each test condition, a set of laser scattering data was recorded with the model retracted and injected into the flow. This produced test data describing the flow field properties in the free-stream flow and then in the local flow field above the blunt 5-deg cone.

This report describes the test apparatus, procedures, and data reduction of the model surface pressures and the millivolt outputs of the optical detectors.

Inquiries to obtain copies should be directed to AEDC/DOT, Arnold Air Force Station, TN 37389. A microfilm record of the test results has been retained in the VKF at AEDC.

## 2.0 APPARATUS

### 2.1 TEST FACILITY

Tunnel B (Fig. 1) is a closed circuit hypersonic wind tunnel with a 50-in. diam test section. Two axisymmetric contoured nozzles are available to provide Mach numbers of 6 and 8 and the tunnel may be operated continuously over a range of pressure levels from 20 to 300 psia at Mach number 6, and 50 to 900 psia at Mach number 8, with air supplied by the VKF main compressor plant. Stagnation temperatures sufficient to avoid air liquefaction in the test section (up to 1,350°R) are obtained through the use of a natural gas fired combustion heater. The entire tunnel (throat, nozzle, test section, and diffuser) is cooled by integral, external water jackets. The tunnel is equipped with a model injection system, which allows removal of the model from the test section while the tunnel remains in operation. A description of the tunnel may be found in the Test Facilities Handbook (Ref. 1).

### 2.2 TEST ARTICLE

The blunt 5-deg cone pressure model shown in Fig. 2 is the standard calibration body for the VKF. This cone which was designed and fabricated in the VKF is nominally 30 in. long with a 6 in. base diam and a 0.375 in. radius nose. Sixty-eight (0.063 in. I.D.) pressure taps were installed in this stainless steel model. The pressure taps are located along four longitudinal rows spaced 90-deg apart with 17 equally spaced pressure taps per row.

This calibration body was installed on a 12-deg prebend model support system as shown in Fig. 3. Variations in the sector center of rotation produces a systematic vertical displacement in the model axis relative to the tunnel axis.

### 2.3 LASER SCATTERING SYSTEM

To accomplish the objective of particulate size distribution and concentration measurements, an extensive optical diagnostics system was designed and installed in Tunnel B. The particular Mie scattering method employed was developed by the PWT/AT Branch. The Mie scattering instrumentation included a Spectra-Physics® argon ion laser with a beam power of approximately two watts at 514.5 nm, five detector units, and a laser receiver power meter as shown in Fig. 4. Each detector unit contained two 1P28 photomultiplier tubes as detectors of the components of scattered and polarized laser light, and each unit was situated at one of five different windows for viewing the light scattered from the flow particles as they encountered laser light in the observation volume. The laser receiver power meter measured the beam transmission through the flow. Data were recorded by the VKF computer. The pattern of scattered light signal amplitudes, polarization states, beam transmission, and detector unit viewing angles uniquely determines the size distribution and concentration, with the added potential of particulate material identification. Size specification accuracy increases with the number of detectors. All these components were mounted on platforms supported by the tunnel's two schlieren vibration-isolation support columns, which are structures independent of the tunnel and located on each side of the test section.

Components of the system located on the nonoperating side of the tunnel are shown in Fig. 5. A steel platform previously used for Tunnel C work was modified and affixed to the vibration-isolation support. The Spectra-Physics laser and three Mie scattering detector units were each mounted on one of two levels of this platform. On the tunnel operating side, two detector units and the laser power meter were mounted on an existing table, and these components are shown in Fig. 6.

A view from within the tunnel test section of the optical components located on the operating and nonoperating sides of the tunnel is shown in Figs. 7 and 8, respectively. The detector unit mounted on top of Tunnel B is shown in Fig. 9a.

Additional optical instrumentation was installed for measurement of the nitrogen molecular number density. A cooled photomultiplier tube (Fig. 9b) located above the tunnel observed Raman scattered radiation from the same observation volume through narrow bandpass and blocking filters, and these signals were recorded by hand.

Finally, an optical system for measuring particulate velocities was added. A Coherent Radiation argon ion laser of approximately 3 watts output of 514.5 nm was mounted alongside the Spectra-Physics laser, and a complex optical system provided a primary and a reference beam from this laser, each intersecting at the observation volume. A Fabry-Perot interferometer, associated optics, and an uncooled photomultiplier tube completed this velocity system; they were mounted on the operating side as shown in Fig. 6d.

## 2.4 STANDARD TEST INSTRUMENTATION

The standard measuring and recording devices, and calibration methods for all the measured parameters other than those associated with the laser scattering system are listed in Table 1. This table also contains the estimated measurement uncertainties. The corresponding information associated with the measuring, recording, and calibration techniques for the laser scattering systems will be documented by PWT/AT in their final report for ARO Project P32M-01.

## 3.0 TEST DESCRIPTION

### 3.1 TEST CONDITIONS AND PROCEDURES

#### 3.1.1 General

A summary of the nominal test conditions are given below.

M	PT, psia	TT $^{\circ}$ R	Min. Dew Pt	U, ft/sec	PT2, psia	RE $\times 10^{-6}$ /ft
7.99	690	1350	-59 $^{\circ}$ F	3878	5.89	3.0
7.98	460	1340	-53 $^{\circ}$ F	3864	3.95	2.0
7.95	232	1360	-52 $^{\circ}$ F	3891	2.03	1.0
7.90	116	1345	-50 $^{\circ}$ F	3868	1.04	0.5

A test log showing all configurations and variables covered in this program is presented in Table 2.

Unless specifically identified in Table 2, all data recorded with the model injected into the tunnel flow were obtained with the model center of rotation at 7.0 inches (see Fig. 3). When the column labeled "Cone in Tank" is checked, free stream laser scattering measurements were recorded. In all other cases, the model was injected into the tunnel flow and either laser data or cone surface pressure measurements were made as indicated in the test log, Table 2.

In the VKF continuous flow wind tunnels (A, B, C), the model is mounted on a sting support mechanism in an installation tank directly underneath the tunnel test section. The tank is separated from the tunnel by a pair of fairing doors and a safety door. When closed, the fairing doors, except for a slot for the pitch sector, cover the opening to the tank and the safety door seals the tunnel from the tank area. After the model is prepared for a data run, the personnel access door to the installation tank is closed, the tank is vented to the tunnel flow, the safety and fairing doors are opened, the model is injected into the airstream, and the fairing doors are closed. After the data are obtained, the model is retracted into the tank and the sequence is reversed with the tank being vented to atmosphere to allow access to the model in preparation for the next run. The sequence is repeated for each configuration change.

The free stream Mach number was confirmed on the basis of the pressure distribution on the VKF standard calibration body, a blunt 5-deg cone. These plotted pressure distributions are given in Fig. 10 and include the theoretical results used in confirming the free stream Mach number. The theoretical results are based on the HVSL (three-dimensional hypersonic viscous shock layer) code based on the work of Lubard and Hellwell (see Refs. 2 and 3). This version of the HVSL provides an estimate of the induced pressure distribution produced on an unyawed blunt nose cone with laminar flow in a hypersonic stream.

### 3.1.2 Test Procedure

Basically the first shift as indicated in Table 2 was devoted to defining the character of the flow when the tunnel dew point (humidity) was high (the order of 0 to +30°F). Cone surface pressure data were taken at each new test condition. The laser scattering data were obtained with the model in the tank to provide free stream results, and then the model was injected into the tunnel flow to obtain similar results in the local flow field over the model downstream of the model bow wave.

The final shift was devoted to obtaining similar data with the tunnel running in a very dry condition. In addition to obtaining laser scattering data with and without the model injected into tunnel flow, a set of results was obtained as the model was moved relative to the laser-optics observation volume (Runs 27 to 30 in Table 2). This sequence of tests was run in an attempt to see if laser scattering measurements could be used to detect the variations in the local static density in the flow field of the blunt cone.

Preceding and following each tunnel shift, a set of air-off laser scattering data was recorded to provide additional calibration results for the optical system.

### 3.1.3 Data Acquisition

The model surface pressure data were obtained by means of an pressure equilibrium technique described in Ref. 4. This required that each pressure readout be scanned 40 times in one second intervals. Based on the geometry of the pressure tubing from the model to the transducer, the nominal temperature of the air in the tubing, and the pressure-time history, the equilibrium pressure at the model surface could be defined.

The laser scattering results consisted of the millivolt output from the 10 photomultiplier detectors, the LILM, the LRPM, and the nitrogen concentration output TOUT. Except for TOUT, the outputs were scanned 300 times at equal time intervals of 0.03 seconds. All other measurements were scanned once for each data run.

## 3.2 DATA REDUCTION

Except for the laser scattering evaluations, all other data reduction procedures were standard. The output from the laser scattering system was converted to millivolts using the proper amplifier gains and scale factors, namely

$$\text{Millivolts} = (0.61035/\text{Gain})\text{Reading}$$

The sampled signal consisting of 300 points was summed and tabulated along with the average value. A tare value, obtained by blocking the laser beam, was obtained prior to each data point. The tare value also consisted of 300 sampled points which were summed and averaged. The tabulated results consist of the tare value, the data point, and the difference between and tare and data point.

### 3.3 MEASUREMENT UNCERTAINTY

In general, instrumentation calibrations and data uncertainty estimates were made using methods recognized by the National Bureau of Standards (NBS) and described in Ref. 5. Measurement uncertainty is a combination of bias and standard deviation defined as:

$$U = t(B + t_{95} S)$$

where B is the bias limit, S is the sample standard deviation, and  $t_{95}$  is the 95th percentile point for the two-tailed Student's "t" distribution which for degrees of freedom greater than 30 is 2.

Estimates of the data uncertainties for the standard tunnel measurements are presented in Table 1. The uncertainty estimates for the laser scattering outputs will be included in the final analysis of the results by PWT/AT.

The bias and standard deviations of the measured data were propagated through the standard data reduction in accordance with Ref. 5. The results are included in Table 1.


### 4.0 DATA PACKAGE PRESENTATION

The data package consists of two data formats, namely, the blunt 5-deg cone surface pressure results and the tabulated laser scattering millivolt outputs. Examples of the two data formats are given in Appendix III.


REFERENCE

1. Test Facilities Handbook (Eleventh Edition). "von Karman Gas Dynamic Facility, Vol. 3," Arnold Engineering Development Center, June 1979.
2. Lubard, S. C. and Helliwell, W. S. "Calculation of the Flow on a Cone at High Angle of Attack." R&D Associates RDA-TR-150, Santa Monica, CA, February 1970.
3. Mayne, Arloe W., Jr. "Calculation of the Laminar Viscous Shock Layer on a Blunt Biconic Body at Incidence to Supersonic and Hypersonic Flow." AEDC-TR-76-123, December 1976.
4. Brown, D. L. "Predicting Equilibrium Pressures from Transient Pressure Data." Aerospace Research Laboratories ARL 65-7, January 1965.
5. Thompson, J. W. and Abernethy, R. B. et al. "Handbook Uncertainty in Gas Turbine Measurements." AEDC-TR-73-5 (AD755356), February 1973.

**APPENDIX I**  
**ILLUSTRATIONS**



a. Tunnel assembly



b. Tunnel test section  
Figure 1. Tunnel B.

All Dimensions in Inches

0.063 I.D. Orifices  
in Four Longitudinal  
Rows Spaced 90 deg Apart




Fig. 2. VKF Standard Cone-Pressure Model




Figure 3. Tunnel B Installation for Laser Scattering Test






Figure 4 Laser - Photomultiplier Detector Installation with Model Injected



a. Optical System Covered  
Figure 5. Dual Laser Installation, Nonoperating Side of Tunnel B



b. Downstream Laser Optics

Figure 5. Continued.



c. Upstream Laser Optics and Detectors  
Figure 5. Concluded.






Figure 6. Laser-Optics Installation on the Operating Side of Tunnel B  
a. Optics Covered




b. Optics Uncovered, Viewed from Above

Figure 6. Continued



c. Optics Uncovered, Viewed Directly into Tunnel Windows  
Figure 6. Continued



d. Downstream View with Fabry-Perot Optics Systems

Figure 6. Concluded.




Figure 7. Laser-Optics System as Viewed from the Tunnel, Operating Side






Figure 8. Laser-Optics System as Viewed within the Tunnel.  
Nonoperating Side

a Mie Scattering Photomultiplier Detectors  
Figure 9. Optical Recording System on Top of Tunnel B







b. Cooled Photomultiplier  
Figure 9. Concluded




a.  $P_T = 685 \text{ psia}$ , Dew Pt =  $+10^{\circ}\text{F}$ , C.R.  $T = 7.00 \text{ in.}$   
Figure 10. 5-Deg Blunt Cone (Calibration Body) Pressure Distributions




b.  $P_T = 685 \text{ psia}$ , Dew Pt. =  $-5^{\circ}\text{F}$ , C.R. = 7.00 in.  
 Figure 10. Continued




c. PT = 685 psia, Dew Pt. =  $-27^{\circ}\text{F}$ , C.R. = 7.00 in.  
Figure 10. Continued



d.  $P_T = 690$  psia, Dew Pt. =  $-59^{\circ}\text{F}$ , C.R. = 0.07 in.  
Figure 10. Continued




e.  $P_T = 686$  psia, Dew Pt. =  $-59^\circ F$ , C.R. = 7.04 in.  
Figure 10. Continued




f.  $P_T = 460 \text{ psia}$ , Dew  $P_T = 153^\circ\text{F}$ , C.R. = 7.04 in.  
Figure 10. Continued


32



g. PT = 228 psia, Dew PT = 22, C.R. = 7.00 in.  
Figure 10. Continued



h.  $P_T = 230 \text{ psia}$ , Dew  $P_T = -25^\circ\text{F}$ , C.R. = .700 in.  
 Figure 10. Continued



- i.  $P_T = 230 \text{ psia}$ , Dew  $P_T = -51^\circ\text{F}$ , C.R. = 0.04 in.
- Figure 10. Concluded

**APPENDIX II**

**TABLES**

TABLE I. ESTIMATED UNCERTAINTIES  
a. Basic Measurements

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT <sup>a</sup>						Method of System Calibration	
	Precision Index (S)	Bias (B)	Uncertainty $\pm (B + t_{95})$		Range	Type of Recording Device		
			Percent of Readings	Percent of Measurement				
PT, psia	+0.02	+0.26	<+0.30	0.38	<104	Bell and Howell Variable Capacitance Transducer	Digital Data Acquisition System (DDAS), Analog to Digital Converter (A/D)	
	+0.02	+0.25	<+0.30	0.30	104-200		End-to-End Calibration of Multiple Pressure Levels Using a Measuring Device Calibrated in the Standards Laboratory	
	+0.11	+0.58	<+0.34	0.30	200-232		NBS Conformity by Voltage Substitution Calibration	
	+0.11	+0.25			232-1000		Heidenhain Rotary Encoder RD700 Resolution = 0.0006 deg	
TT, °F	±1	±0.375	<0.8	4	32-530	Chromel-Alumel Thermocouple	Overall Accuracy = 0.001 deg	
	±1	±0.375			530-2300		End-to-End Calibration of Multiple Pressure Levels Using Air Weight Tester	
ALPHA, deg	+0.025	0		0.05	-3 to 27	Potentiometer	Comparison to Facility Standard Periodically Checked Against Interlab Standard	
PT, psia Standard Pressure Systems	0.00075 0.002 0.005 0.2	0.3 0.2 0.2	(0.35 ± .0015 psia) (0.25 ± .004 psia) (0.2% ± .010 psia)	<1 ≤5 ≥15		Baratron WIACMO Variable Reluctance Transducers		
PTEF, μHg.	±25	Not Defined		±50	<1000	Heating Vacuum Gauge		
DNF Pt, °F	±2.5			±5		DUPONT S10 Moisture Analyzer		

Thompson, J. V. and Abernethy, R. M. et al. "Handbook Uncertainty in Gas Turbine Measurements," ADDC-TR-73-6 (AD 755159), February 1973.

TABLE I. Concluded  
b. Calculated Parameters

Parameter Designation	STEADY-STATE ESTIMATED MEASUREMENT*					
	Precision Index (S)	Bias (B)	Uncertainty $\pm(B + t_{953})$		Percent of Reading	Percent of Measurement
		Unit of Measure-ment	Unit of Measure-ment			
M	0.010	0	0.020	$3.0 \times 10^6$		
P, psia	$\pm 0.81$	$\pm 0.25$	$\pm 1.87$			
PT2, psia	$\pm 0.56$	$\pm 0.25$	$\pm 1.37$			
RE, ft $^{-1}$	$\pm 0.37$	$\pm 0.43$	$\pm 1.17$			
RHO, lbm/ft $^3$	$\pm 0.58$	$\pm 0.35$	$\pm 1.51$			
U, ft/sec	$\pm 0.04$	$\pm 0.12$	$\pm 0.20$			

Abernathy, R. S. et al. and Thompson, J. W. "Handbook Uncertainty in Gas Turbine Measurements." AFDC-TR-73-5 (AD 755388), February 1973.

TABLE 2 .  
VKF TUNNEL TEST LOG

USER PWT / ATO		PROJECT TITLE AEROC/DOKE Laser Scattering Applications Development										DATE 16 Jan '80	
REPRESENTATIVES L.L. Price, R.P. Weaver		PROJECT PERSONNEL										ARO TEST PERSONNEL W.T. Strike, D.R. Wagner	
MODEL 8° Blunt Cone (Calibration Body)													
Run	Configuration	Config Confirmed	M	PT psi	T °F	a <sub>0</sub> deg	Dew pt	Laser Date	Cone Date	Cone done in Tank	Time	Remarks	
1	Laser/Cone	✓/✓	0	14.1	79	0	-	✓	✓	✓	1519	Laser Scan 100% Done, per pt.	
2											1539	LRPH Gain 1.5	
3											1600		
4											1646	Tunnel Evacuated	
5											1742	Laser Gain 1, Dryers out of Tunnel Circuit	
6											1750	D.R. changing -23 to +18, when -3 of	
7											1758		
8											1802		
9											1824		
10											1858		
11											1911		
12											1912	Dryers added to circuit	
13											2001		
14											2014		
15											2020		
16											2025		
17											2027		
18											2059		
19											2105		
20											2107		

NOMENCLATURE. Cone Done means cone surface precision is met.

Gains 1, 2, 3, 4, 5 to 200% inc 10%, P.D.M is 1000. Gain 4 to L.T.D is 1.0  
Run 7 to 9 D.R Oscillation, 2mm cycles from +16.0 to +2.0% (D.R. is Dev Pt)

**TABLE 2.**   Continued

VKF TUNNEL		TEST LOG		PROJECT TITLE AEDC/DOTR Laser Scattering Applications Development										
USER	PWT / ATD	REPRESENTATIVE	2.4. Price, DR Weller	MODEL	8" Blank Cone (Calibration Body)	CONF.	PT psia	T <sub>AT</sub> °F	a, deg	Dew Pt °F	Laser Date	Cone in Tank	Time	Remarks
21	Laser/Cone	✓	0	0.8	80	✓						✓	0927	
22		✓	↓	14.4	↓	✓						✓	0933	
80-23				Calibration Curves on	17 Jan 80									
80-24				0	14.4	80	✓					✓		
80-25							✓					✓		
80-26							✓					✓		
80-27						↓	↓	↓				✓		
80-28						0	14.4	80				✓	0917	
80-29						0	0.7					✓	0923	
80														unable to control laser during connections in sh. box. test error on sh. box 2 hrs. of operation. Dew pt = 24°F Dew pt variation, if present, is -30°F. Dew pt at plant is -50°F

Verz. 2 (9/17)

TABLE 2. . Continued  
 VKF TUNNEL Z TEST LOG

100

TABLE 2. Concluded

NOMENCLATURE 11.2 ~ West Cliffs, and

**APPENDIX III**  
**DATA PACKAGE FORMATS**

## LASER SCATTERING APPLICATIONS DEVELOPMENT

PAGE 1

RUN 45

M = 7.98

PES = 2.02E-06

DATA TYPE=2

PT(PSIA) = 460.1

TT(DEG-R) = 1342.

ORIFICK  
No.X  
(IN.)

S/R/N

OMEGA  
(DEG)P<sub>N</sub>P<sub>H</sub>/PP<sub>H</sub>/PT2P<sub>H</sub>/PNNP<sub>M</sub>/PMFP<sub>M</sub>/PMFP<sub>M</sub>/PM

K

CENTER OF ROTATION = 7.04

FROST POINT(DEGF) = -53.

ALPHA(DFG) = -12.03

PROJECT NUMBER V41B-45

DATE COMP. 18-FEB-80  
 TIME COMP. 13:38:109  
 DATE RECORDED 12-FEB-80  
 TIME RECORDED 21:03:0  
 PROJECT NUMBER V41B-45

UNCLASSIFIED

- a. Page 1  
 1. Typical Pressure Distribution Tabulation

DATE COMPUTED 18-FEB-80  
 TIME COMPL. 13:38:12  
 DATE RECORDED 12-FEB-80  
 TIME RECORDED 21503 8  
 PROJECT NUMBER V41B-45

LASER SCATTERING APPLICATIONS DEVELOPMENT

PAGE 3

PUN = 7.98  
P = 460.1  
RE = 2.07E+06

DATA TYPE=2  
P1(P5IA) = 1342.  
TTNEG-RJ =

PROJECT NUMBER V41B-45

RH(CINCHHS)=0.375  
PTS(PSIA)= 3.950

CENTER OF RUTATION = 7.84  
FROST POINT(DG-F)= -53.  
ALPHA(DRG)= -12.03

ORIFICE #	X (IN.)	S/RN	WNEGA (DEG)	PW	PW/P	PW/PY2	PW/PNN	PW/PMP	PW/PWF	PW/PWF	PW/PWN	K
3	5.140	3.812	180.0	0.1547	3.229	0.0392	0.0382	0.9996	0.9228	0.0006	0.4222	
11	8.570	12.993	180.0	0.0868	1.113	0.0220	0.0215	1.0014	0.9341	0.0013	0.4332	
23	13.720	26.780	180.0	0.0426	1.724	0.0209	0.0204	1.0032	0.9410	0.0011	0.3771	
31	17.150	35.961	180.0	0.0864	1.783	0.0216	0.0211	1.0015	0.9340	0.0010	0.4396	
39	20.580	45.143	180.0	0.0893	1.864	0.0226	0.0221	1.0005	0.9787	-0.0003	0.3829	
43	27.290	49.720	180.0	0.0893	1.864	0.0226	0.0221	1.0003	0.9660	0.0005	0.4726	
47	24.000	54.298	180.0	0.0910	1.899	0.0230	0.0225	1.0005	0.9493	0.0006	0.4815	
51	25.720	58.902	180.0	0.0907	1.893	0.0230	0.0224	1.0002	0.9340	0.0007	0.5068	
55	27.430	63.479	180.0	1.944	1.943	0.0236	0.0230	0.9565	0.9006	0.0006	0.4582	
59	29.420	68.806	180.0	0.0910	1.900	0.0230	0.0225	0.9970	1.2007	0.0010	0.5282	
63	30.860	72.661	180.0	0.0910	1.960	0.0230	0.0225	1.0010	0.9113	0.0006	0.5265	
4	5.140	3.812	270.0	0.1542	3.220	0.0390	0.0381	1.0002	0.9316	0.0004	0.4017	
16	10.290	17.598	270.0	0.0828	1.728	0.0210	0.0205	0.9991	1.4469	0.0054	0.4301	
24	15.430	31.357	270.0	0.0436	1.746	0.0212	0.0207	0.9998	1.3615	0.0023	0.4419	
32	17.150	35.961	270.0	0.0447	1.768	0.0214	0.0209	1.0017	0.9355	0.0006	0.4533	
36	18.860	40.539	270.0	0.0470	1.816	0.0220	0.0215	0.9920	1.3859	0.0018	0.4558	
40	20.580	45.143	270.0	0.0482	1.841	0.0223	0.0218	1.0006	0.9888	0.0002	0.3645	
48	24.000	54.298	270.0	0.0593	1.864	0.0226	0.0221	1.0010	0.9619	0.0005	0.4239	
52	25.720	58.902	270.0	0.0491	1.861	0.0226	0.0220	1.0003	0.9521	0.0004	0.5139	
56	27.430	63.479	270.0	0.0919	1.919	0.0233	0.0227	1.0004	0.9576	0.0003	0.4891	
60	29.420	68.806	270.0	0.0903	1.864	0.0226	0.0221	1.0005	0.9799	0.0025	0.9405	
64	30.860	72.661	270.0	0.0889	1.856	0.0225	0.0220	0.9989	0.9152	0.0021	0.6265	
68	32.580	77.265	270.0	0.0893	1.877	0.0228	0.0222	1.0005	0.9556	0.0004	0.5106	

NOSE PRESSURE

69 3.716 0.001 0.0 4.0438 84.413 1.0238. 1.0000 1.000q

b. Page 2

1. Concluded

DATE COMP "D" 18-FEB-80  
 TIME COMP J 1:37:44  
 DATE RECORDED 12-FEB-80  
 TIME RECORDED 2:45:20  
 PROJECT NUMBER V41B-45

UNCLASIFIED  
 UNCLASSIFIED

#### LASEP SCATTERING APPLICATIONS DEVELOPMENT

PAGE 1

RUN 44  
 N = 7.98  
 DE = 2.02E+06

DATA TYPE=1  
 PT(PSTA) = 459.6  
 TR(NEG-R) = 1342.

PROJECT NUMBER V41B-45

RM(INCHES)=0.375  
 PTS(PSTA)= 3.945

#### LASER SCATTERING MEASUREMENTS

NUMBER OF SAMPLES = 300

TIME BASE (SEC) = 10.0

	AVERAGE TARE	SUM	AVERAGE READING SUM	AVERAGE DELTA SUM
TOUT	1.4664E+04	1.8864E+04	1.3673E+06	1.3485E+06
LTLN	3.6576E+02	1.0973E+05	3.6644E+02	3.6644E+02
LSPH	-9.7371E-01	-2.9211E+02	9.0899E+01	9.1872E+01
RAT10				25.07 %

P01	9.3953E-01	2.8186E+02	-1.4394E+02	-4.3182E+04	-1.4488E+02	-4.3464E+04
P02	5.7983E-02	1.7395E+01	-3.8374E+00	-1.1514E+03	-3.8895E+00	-1.1698E+03
P03	2.1937E-01	6.5796E+01	-9.9772E+01	-2.9932E+04	-9.9991E+01	-2.9993E+04
P04	-5.6152E-03	-1.6846E+00	-1.6298E-01	-4.8895E+01	-1.5737E-01	-4.7211E+01
P05	8.1787E-02	2.4516E+01	-4.1972E+00	-1.2929E+03	-4.2790E+00	-1.2337E+03
P06	-5.0639E-01	-1.5192E+02	-3.3440E+00	-1.0152E+03	-2.8776E+00	-8.6328E+02
P07	3.3549E-01	1.0065E+02	-6.5216E+01	-1.9565E+04	-6.5551E+01	-1.9665E+04
P08	-7.1106E-01	-2.1332E+02	-5.1634E+01	-1.5490E+04	-5.0923E+01	-1.5277E+04
P09	-2.9555E+01	-8.7465E+03	-1.0889E+02	-3.2668E+04	-7.9738E+01	-2.3921E+04
P10	-1.9326E-03	-5.7963E+01	-4.8499E+00	-1.4549E+03	-4.8479E+00	-1.4544E+03

a, Summary Sheet

2. Typical Laser-Optics Tabulation

\*\* TANKS FOR RUN NO 44 \*\*

NO OF LOOPS = 360

TOUT	AVERAGE VALUES	SUMS
L1LM	1.98641	100641
LAPM	365.76	0.0973E+06
	-0.97371	-292.11

PURE-PHOTOMULTIPLIER READINGS

	AVERAGE VALUES	SUMS
PD1	0.93053	281.46
PD2	0.57981E-01	17.395
PD3	0.21312	65.746
PD4	-0.56152E-02	-1.6816
PD5	0.81167E-01	24.536
PD6	-0.56139	-151.97
PD7	0.33349	106.65
PD8	-0.71106	-213.32
PD9	-29.155	-8746.5
PD10	-0.19328E-02	-0.579813

\*\*\*\* RAW COUNTS, SCALE FACTOR AND GAINS \*\*\*\*

TOUT	AVERAGE VALUES	SUMS
L1LM	18944.0	18944.
LAPM	5992.5	5992.
	-16.0	-476.

PURE-PHOTOMULTIPLIER

	AVERAGE VALUES	SUMS
PD1	15.4	461.6
PD2	1.0	285.
PD3	3.6	1078.
PD4	-0.9	-276.
PD5	1.3	402.
PD6	-8.3	-2489.
PD7	5.5	1649.
PD8	-11.6	-3495.
PD9	-477.9	-14307.
PD10	-0.3	-95.

	S FAC	GAIN	S/F/GAIN
L1LM	1.000000000	1.00	1.000000
LAPM	.61035156	10.00	.061035
	.61035156	10.00	.061035

b. Gains/Scale Factor Tabulations  
2. Concluded

